

FREE FIELD CHECKLIST

THE 25 DRYWALL KILLERS

The 25 misses most likely to cause a drywall removal, a cabinet delay, a trade callback, a failed inspection, a warranty claim — or a Tarion conversation.

WHAT THIS LIST PREVENTS

- Drywall removals
- Cabinet delays
- Trade callbacks
- Failed inspections
- Warranty claims
- Tarion conversations

Walk it before insulation. Walk it again before drywall.

Built for production residential Site Supervisors, Assistant Supervisors, and Coordinators.

Most construction problems aren't caused by major mistakes — they're caused by small misses that get covered up. A bulkhead out of level. A shower valve off-centre. A missing backing. A crushed dryer vent. **Cheap to fix before drywall. Expensive after.** Use this before insulation, and again before board.

LIGHTING & ELECTRICAL COMMON MISS

- ☐ Potlights installed per approved layout
- ☐ Island pendants centred to island
- ☐ Vanity lighting centred to vanity
- ☐ EV charger rough-in complete
- ☐ TV / data / security rough-ins installed
- ☐ Smoke & CO devices located correctly
- ☐ Nail plates installed where required

PLUMBING HIGH COST

- ☐ Tub and shower base level and fully supported
- ☐ Shower valve centred and correct height
- ☐ Vanity drain centred to cabinet layout
- ☐ Laundry box centred and level
- ☐ Fridge waterline installed

HVAC HIGH COST

- ☐ Ducts connected and secure
- ☐ Return air openings complete
- ☐ Bathroom exhaust connected to roof cap
- ☐ Range hood vent centred to appliance location
- ☐ Dryer vent complete and unobstructed

FRAMING & STRUCTURE**HIGH COST**

- ☐ Kitchen bulkheads level, plumb and square
- ☐ Subfloor squeaks repaired
- ☐ No damaged trusses, joists or structural members
- ☐ Fire separations complete
- ☐ Fireplace opening matches manufacturer specifications

BACKING & EXTRAS**COMMON MISS**

- ☐ Cabinet backing installed
- ☐ Stair and handrail backing installed
- ☐ Grab-bar backing installed
- ☐ TV backing installed
- ☐ Schedule Z / extras verified

MOST MISSED ITEM**Kitchen Bulkheads**

Many bulkheads look acceptable during framing but become obvious once cabinets go in. Uneven cabinet gaps are one of the most common homeowner deficiency items. Before you release the house, check:

- Floor-to-bulkhead dimensions
- Ceiling-to-bulkhead dimensions
- Cabinet layout dimensions
- End conditions
- Overall straightness

SITE SUPER RULE

If it costs 10 minutes to fix today and \$1,000 to fix after drywall — fix it today.

- | | |
|-----------------------|-------------------------|
| • A drywall removal | • A warranty issue |
| • A failed inspection | • A trade callback |
| • A cabinet delay | • A homeowner complaint |

Don't hide a problem behind board to protect a schedule. Re-check every correction before you release the house.

THIS IS THE SHORT LIST

The full system catches **the rest.**

THE BUILDERPILOT PRE-DRYWALL RELEASE SYSTEM INCLUDES

- ✓ Room-by-room inspection walks
- ✓ Framing quality inspection checklist
- ✓ HVAC verification walk
- ✓ Plumbing verification walk
- ✓ Electrical verification walk
- ✓ Trade sign-off forms
- ✓ Bulkhead & cabinet layout verification
- ✓ Extras & Schedule Z tracker
- ✓ Deficiency log
- ✓ Insulation release form
- ✓ Drywall release form
- ✓ Site supervisor release process

Walk. Verify. Release.

Get the full system at **BuilderPilot**

builderpilot.gumroad.com